



- NOTES:**
1. ALL TIMBERS ARE 200 x 200 x 1800 EXCEPT AS NOTED
  2. ALL LAPS TO BE MADE IN DIRECTION OF TRAFFIC
  3. ALL MEASUREMENTS IN MILLIMETRES
  4. ALL JOINTS TO BE LAPPED IN THE DIRECTION OF TRAFFIC
  5. TURNED DOWN TERMINALS ARE TO BE USED AT BOTH ENDS OF GUARDRAIL



<b>SD-700-04-03</b>	
<b>STEEL W-BEAM GUARDRAIL TURNED DOWN TERMINAL INSTALLATION DETAIL</b>	
Date: <b>JULY 1996</b>	Revised: <b>MARCH 2002</b>

Approved  
*K. Chiodo*  
 Director  
 Highways Division

APR 21 2005  
 Date